BANGALORE DIVISION.

Notice dated 31st December 1928.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore Division, up to 2 P.M., on 15th January 1929, for restoring Tattanur, Balanakere, Reg. No. 54 of Hoskote Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. to 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

3a. Percentages less or above estimated rates will not be accepted.

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of rupees one hundred and fifty in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Tattanur-Balanakere of Hoskote Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the Notice Board in the Executive Engineer's Office in due course. No enrequiries regarding the acceptance or rejection of a tender will receivce any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract for restoring Tattanur-Balankere Tank Reg. No. 54 of Hoskote Taluk.

No.	Items of work	Per	Quantity	Rate
	Bund R. L. 55·00 top width 4 feet.			
1	Clearing the jungle and cutting grips	Grade	18	
2	Earthwork to bund including watering and tamping and also lead and lift.	C.yd.	5011	
3	Rough stone revetment (new)	,,	361	
4	Dismantling and rebuilding old stones with new jelly and etc.	,,	210	
5	Turfing	S.yds.	3995	
6	Providing new grade stones with cutting figures and painting.	Each	19	
7	Do index stones	,,	19	
8	Do Register number stones	,,	1	
9	Do B. M. stones...	,,	2	
10	Conveying earth from waste weir to bund ...	C.yds.	682	
	Constructing a sluice at R. L. 46·00.			
1	Cut opening the bund and refilling	C.yds.	43	
2	Earthwork (excavating the foundation)	,,	16	
3	Surki mortar concerte	C.ft.	319	
4	Brick (burnt) in surki mortar	,,	357	
5	Burnt stone slabs 6" thick dressed and fixed ...	S.ft.	172	
6	Surki mortar pointing	Sqr.	0·50	
7	Plastering with surki mortar	,,	2·28	
8	Cutting holes in slabs	Each	3	
9	Providing plug and rod with looking arrangements ...	Lump	sum	
	Constructing a waste weir.			
1	Earthwork (excavation)	C.yds.	682	
2	Surki in mortar concerte	C.ft.	388	
3	Burnt brick in surki mortar	,,	895	
4	Burnt stone slabs 6" thick dressed and fixed ...	S.ft.	236	
5	Surki mortar plastering	Sqr.	8·71	
6	Rough stone work, new	C.yds.	141	

Notice dated 31st December 1928.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore Division, up to 2 P.M. on 15th January 1929, for restoring Nanjapur-Oormundinakere Reg. No. 155 of Anekal Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. to 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

Description of work	Unit of work	Rate per unit

3*a*. Percentages less or above estimated rates will not be accepted.

4. Each tender must be accompanied by a deposit of rupees one hundred and fifty in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Nanjapur-Oormundinakere of Anekal Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Estimate for restoring Nanjapur Tank Reg. No. 155 of Anekal Taluk.

No.	Items of work	Per	Quantity	Rate
	Bund R. L. 56·50 top width 4 feet.			
1	Cutting grips	Grade	15	
2	Earthwork with watering and tamping with lift and lead.	C.yds.	5126	
3	New stone work	,,	382	
4	Old stone work with new jelly of	,,	120	
5	Turfing	S.ft.	4192	
6	Examining the percolation and putting puddle mixed with gravel including excavation of	C.ft.	269	
7	Providing new grade stones and cutting figures, numbering and painting of	Each	15	
8	Providing new index stones	,,	15	
9	Do Register No. stones	,,	1	
10	Do B. M. stones	,,	2	
11	Do gauge stones	,,	1	
	Sluice.			
1	Repairing the existing sluice with locking arrangements.	Lump	sum	
	Waste weir to the right 22 feet long and raising the crest to R. L. 52·00.			
1	Dismantling the damaged masonry returns and steps with coping slabs.	Lump	sum	
2	Burnt brick in surki mortar	C.ft.	149	
3	Refixing coping slabs with surki mortar ...	S.ft.	34	
4	Plastering with surki mortar	,,	3·01	
5	Burnt stone slabs roughly dressed	Sqr.	19	
6	Jelly concrete with surki mortar	C.ft.	53	

No.	Items of work	Per	Quantity	Rate
	Wasteweir to the left 53 feet long R. L. 52·000.			
1	Earthwork excavation	C.yds.	79	
2	Dismantling damaged portion of returns and coping slabs of.	Lump	sum	
3	Burnt brick in surki mortar	C.ft.	294	
4	Re-fixing the old burnt stone slabs	S.ft.	44	
5	Burnt stone slabs roughly dressed new ...	,,	57	
6	Plastering with surki mortar	Sqr.	3 86	
7	Jelly concrete with surki mortar	C.ft.	112	
8	Rough stone work (new)	C.yds.	74	
9	Constructing a masonry retaining wall between old and new apron to the required level.	Lump	sum	

H. R. VENKATASUBBA RAO,
Executive Engineer

KOLAR DIVISION.

Dated 24th December 1928.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., on 24th January 1929, for restoring Geraddi Tank Registered No. 48 of Sidlaghatta Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A M to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of rupees (350) three hundred and fifty in cash or Government Promissory Notes, as earnest money, and be superscribed" Tender for restoring Geraddi Tank Registered No. 48 of Sidlaghatta Taluk in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9' The tenderers must quote specific rates for each item of work both in words and figures.

10. The tenderers stating that the work would be executed at a certain percentage in excess or lower than the estimate rate will not be accepted.